Browned Samuel

# Tabor Avenue Repaving & Safety Project

November 2, 2023 Lawncrest RCO Presentation



11/2/2023



### Who are we?

#### **Office of Complete Streets**

A Division of the Office of Transportation, Infrastructure, and Sustainability

#### **Mission Statement:**


Whether by bus, by bike, on foot, or by car, the Office of Complete Streets is leading innovation and engagement to ensure Philadelphians of all ages and abilities can travel safely.



## Why now?

The Philadelphia Water Department is completing the Tabor Avenue Greening Project.

After construction is complete, the street will be repaved.



PWD is installing tree trenches and tree pits as part of its GSI project

Source: Google Street View



OFFICE OF TRANSPORTATION INFRASTRUCTURE & SUSTAINABILITY



### Tabor Avenue Has a Traffic Safety Problem



**31** People injured

**100** People involved in collisions

Source: 2018-2022 PennDOT Crash Data

OFFICE OF TRANSPORTATION INFRASTRUCTURE & SUSTAINABILITY






### Speeding is a Major Issue

## 73% Drivers traveling over the 30-mph speed limit

6% Drivers traveling greater than 40-mph



Source: 2023 radar speed survey

OFFICE OF **4** TRANSPORTATION, INFRASTRUCTURE & SUSTAINABILITY



### Tabor Avenue Bike/Trail Connections

New bike lanes and safer pedestrian facilities on Tabor Avenue will connect neighbors to area amenities, playgrounds, & the Tacony Creek Trail via the existing bike network.



TRANSPORTATION

& SUSTAINABILITY

INFRASTRU



Paving Phase



11/2/2023

Tabor Avenue Safety Project

### Tabor Avenue Improvements: Repaving

#### **Proposed:**

- 10' two-way bikeway on east side
- buffered and parkingprotected bike lane


No parking lanes are lost

#### Existing road layout (typical)

#### റ്റ So P $\overline{\phantom{a}}$ $\hat{U}$ $\hat{\mathbf{n}}$ $\hat{V}$ Ŷ

#### Proposed road layout (typical)







OFFICE OF & SUSTAINABILITY

### **Changes Based on Your Feedback:**



**Retain the parking** between Devereaux and Robbins - Design Revised



Accommodate high right-turn volumes from Tabor to Levick -Design Revised



Existing conditions at Tabor and Levick (looking south), showing vehicles queued for the northbound right turn

Source: Google Street View

OFFICE O & SUSTAINABILITY


### Changes Based on Your Feedback:



**Plant more trees** - Tree planting included in PWD project. *Additional locations may be added to next phase.* 

$\checkmark$
--------------

**Ensure smooth transition** from the two-way bike lane to 1-way bike lanes. *Will be incorporated into final design.* 



A potential design for safe transitions where a two-way bikeway ends/begins.

Source: City of Minneapolis Street Design Guide



Install a more **protective and durable** alternative to flex posts




Add more traffic calming



Outside of the scope of repaving

Add new crosswalk(s) and modify signals

OFFICE OF TRANSPORTATION INFRASTRUCTURE & SUSTAINABILITY



OFFICE OF TRANSPORTATION INFRASTRUCTURE & SUSTAINABILITY



Tabor Avenue Safety Project



### **Capital Phase**



Tabor Avenue Safety Project



## What is a Capital Project?

- Larger-scale public works project
- Allows for permanent treatments in the right-of-way
- Funded & delivered separate from paving
- Timeline: 3-5 years
- Can Include:
  - Concrete curbs
  - Traffic signals
  - Etc.

# What would you like to see?

An Activity to Refine the Project

OFFICE OF TRANSPORTATION INFRASTRUCTURE & SUSTAINABILITY




11/2/2023



**Tabor Avenue** Godfrey Avenue to Levick Street Safety Improvements Capital Project

1. Crosswalks may be added to some intersections as a part of the capital plan. At which two intersections would you most like to see new crosswalks?

2. Where should the safety improvements be installed? Please use the symbols below to indicate your preferred locations. Please feel free to mark any other suggestions or comments on the maps.



### **Next Steps**



We are asking for your support for the repaving phase of this project, which would be implemented after PWD's work is complete.

Using your feedback, we'll continue revising the ideas for the capital phase of the project. The City will continue to pursue funding for the project and will return in 2024 to continue the conversation.







### **Thank You!**

For questions, please contact:

Andrew Simpson Complete Streets District Manager Andrew.Simpson@phila.gov

